SCHEDULE OF ROOM FINISHES

ROOM	Nº	FLOOR	BASE	WAINS.	WAINS. CAP	WALLS	CEILING	REMARKS
CLOSETS	SAME FINISH AS ADJACENT ROOM							WOOD SHELVES AS NOTED
CORRIDOR	411-415 433-445	ASP.T.	GSFT	GSFT 1'-10½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED ACCOUS.	
DAYROOM	401-403 407-409 431-451 453	ASP.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	
EXAMINING	430	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	HANGING CABINET WITH SLOPING TOP
HOUSEKEEPER'S	410-444	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED PLASTER	SOAPSTONE SHELF
ISOLATION	419-420 421-437 438-439	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED ACCOUS.	
KITCHEN	423	QT.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED ACCOUS.	HANGING CABINET WITH SLOPING TOP
LINEN	412-425 442	ASP.T.	GS.FT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	METAL SHELVING ON BUILT-IN CONC. PLATFORM GSFT BASE- SEE NOTE 425
LOBBY	426	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	
NURSES STATION	404-450	ASP.T.	GSFT	GSFT 1'-10½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED ACCOUS.	MEDICINE CABINET & COUNTER - SEE SHT. 17 FOR DETAILS
SHOWER	407-447	ABR.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED ACCOUS.	SOAPSTONE SHOWER STALLS - SEE SHT. 17 FOR DETAILS
DRESSING	408-446	ABR.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED ACCOUS.	PIN RAILS ON 7'-2½" GSFT PARTITIONS AS NOTED
SINGLE-BED	422-434 435	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	
SINK	405-449	CER.T.	GSFT	GSFT 1'-10½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED ACCOUS.	SOAPSTONE SHELVES SEE SHEET NO 17
STAIR	1-2-3	SOAP-STONE	USFT. NO CODE	USFT	USFT FLUSH	USFT.	CONCRETE STAIR & LINING	SOAPSTONE TREADS AND PLATFORMS FURRED CEILING IN STAIR NO 2 & NO 3
MALE ATTENDANTS TOILET	424	CER.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	K.C. ABOVE WAINS.	FURRED PLASTER	SOAPSTONE TOILET PARTITIONS 60" HIGH CUBICLE DOOR
MENS' TOILET	414	CER.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	ABOVE WAINS.	FURRED PLASTER	SOAPSTONE TOILET PARTITIONS
NURSES TOILET	426	CER.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	ABOVE WAINS.	FURRED PLASTER	SOAPSTONE TOILET PARTITIONS-60" HIGH CUBICLE DOOR
WOMENS' TOILET	440	CER.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED PLASTER	SOAPSTONE TOILET PARTITIONS
UTILITY	406-448	CER.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED ACCOUS.	SOAPSTONE SHELVES HANGING CABINET WITH SLOPING TOP
VESTIBULE	418-436	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	
WARDS	402-416 432-452	ASP.T. & TER. AS NOTED	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	3'-11" HIGH GSFT PARTITIONS AS NOTED
WHEELCHAIR STORAGE	413-441	ASP.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED ACCOUS.	
WHEELCHAIR STORAGE	427	TER.	GSFT	GSFT 7'-2½" HIGH	GSFT	PLASTER ABOVE WAINS.	FURRED PLASTER	
SHOWER & TUB ROOM	409-448	ABR.T.	GSFT	GSFT 7'-2½" HIGH	GSFT	USFT. ABOVE WAINS.	FURRED K.C.	SOAPSTONE LINED SHOWER STALL.

SOAPSTONE CHANGED TO SLATE EXCEPT IN STAIRS

GENERAL NOTES

ENTIRE FOURTH FLOOR CEILING SHALL BE FURRED.

SEE SHEET Nº 1 FOR ABBREVIATIONS & MATERIAL SCHEDULE.

SEE SHEET Nº 4 FOR COMPLETE EXTERIOR DIMENSIONS.

SEE SHEET Nº 8 FOR DOOR DETAILS - DOOR WIDTHS ARE SHOWN ON PLANS - ALL INTERIOR DOOR FRAMES ARE HOLLOW METAL.

FOR HEIGHTS OF WINDOWS SEE ELEVATIONS AND DETAILS.

ALL PARTITIONS SHALL BE 6" THICK UNLESS OTHERWISE NOTED.

SEE STRUCTURAL DRAWINGS FOR DETAIL OF STEEL STRUT AT ENDS OF ALL 3'-11" HIGH MASONRY PARTITIONS.

CENTRAL SECTION BUILDING N-7

WOMENS' WING BUILDINGS N-6 & N-7

MENS' WING BUILDINGS N-6 & N-7

CENTRAL SECTION BUILDING N-6

APPROVED
Commonwealth of Pennsylvania
DEPARTMENT OF WELFARE
BUREAU OF INSTITUTIONAL MANAGEMENT.
Architect [illegible] Date 10-22-41
Secretary [illegible] Date

APPROVED
Commonwealth of Pennsylvania
Department of Labor & Industry
Bureau of Inspection
Buildings Section
Checked By M. S.
Approved By H. D. Day Chief
Approval Date 10-22-41

THE GENERAL STATE AUTHORITY	
APPROVED	EXECUTIVE DIRECTOR
APPROVED	CHIEF ENGINEER
SUBMITTED	ARCHITECT
ACCEPTED	CONTRACTOR
ACCEPTED	CONTRACTOR
ACCEPTED	CONTRACTOR

REGISTERED ARCHITECT PENNSYLVANIA GEORGE W. PEPPER, JR. No. 1780

REVISED TO JOB CONDITIONS JUNE 30 1945

G. S. A. PROJECT NO. 80 B

FOURTH FLOOR PLANS

SENILE BUILDINGS N-6 & N-7
FOR THE
PHILADELPHIA STATE HOSPITAL
PHILADELPHIA PENNSYLVANIA

GEORGE W. PEPPER, JR. REGISTERED ARCHITECT
1600 WALNUT STREET PHILADELPHIA, PA.

DATE AUGUST 20-1941
SCALE 3/8"=1'-0"

THE GENERAL STATE AUTHORITY
ARTHUR H. JAMES PRESIDENT
WILLIAM S. LIVENGOOD, JR. SECRETARY
DAVID H. DIEHL EXEC. DIRECTOR
HARRISBURG, PENNSYLVANIA

SHEET No. 6