NOTE: BURB FOR PIC HAS ON ROOF ABOVE SALLYPORT SHALL BE SUPPLIED BY ELECT. CONTRACTOR, BUT INSTALLED BY G.C.. SEE DET. 2/M3

NORTH

NEW DINING ROOM 109A

SOILED LINEN 222

STORAGE 222A

CORR. 227

CORR. 225

TOILET 228

NEW 8' CHU DURBOND TO REPLACE NEW METAL DOOR BUCK BY CHANGE ORDER

CORRIDOR 230

CLERICAL OFFICES 231

PHYS. 232

UTILITIES 233

CORRIDOR 234

CORRIDOR 235

CORRIDOR 236

CORRIDOR 237

MEDICAL EXAM 238

DENTAL EXAM 239

X-RAY 240

TOILET 241

UTILITY 242

VISITORS 243

LAUNDRY 244

NEW STAIR (SEE A-7)

NURSES STATION 245

CORR. 246

CORR. 247

TOILET 248

NEW 8' CHU DURBOND TO REPLACE NEW METAL DOOR BUCK BY CHANGE ORDER.

OFFICE 250

NOTE:

- SLEEPING ROOMS INDICATED THUSLY ARE LOCATIONS WHERE EXISTING TERRAZZO FLOORS WILL BE REFINISHED, SEE SPEC. SEC. 9D. THERE ARE A TOTAL OF 22 OF THESE ROOMS IN THE CONTRACT.

SECOND FLOOR PLAN

1/16" = 1'-0"

SECURITY SYSTEM LEGEND

- ELECT. STRIKE & HINGE SWITCH.
- KEY-OPERATED INTERCOM.
- CLOSED CIRCUIT TV CAMERA.
- KEY BOX, MARKED TO INDICATE SPARE/CIRCUIT CIRCUIT. BOX WILL HOLD KEY TO OVERRIDE THE EXIT DOOR'S ELECTRICAL STRIKE.

NOTE: THIS WORK IS IN THE ELEC. CONTRACT AND IS SHOWN HERE FOR INFORMATION ONLY.

LEGEND:

- INDICATES NEW OR EXTENDED PARTITION. ON 1/16" SCALE PLAN, SEE 1/8" PLAN FOR ADDITIONAL INFORMATION.
- INDICATES EXIST. G.S.T. PARTITION EXTENDED APPROX. 2'-0" TO UNDERSIDE OF STRUCTURE. FOR ALL SHEETS.

NOTES:

CONTRACTORS SHALL CHECK AND VERIFY ALL EXISTING CONDITIONS PERTAINING TO THE DESIGNATED WORK AT THE SITE. CONTRACTORS SHALL IMMEDIATELY NOTIFY THE ARCHITECT OF ANY FIELD CONDITIONS WHICH DEVIATE FROM THOSE SHOWN ON THE DRAWINGS.

1	POSITIONAL CHU FRAME	
2		
3		
	DESCRIPTION	DESCRIPTION

AS BUILT REVISIONS

SUBMITTED: ARCHITECT (ENGINEER)

SUBMITTED: ENGINEER (ARCHITECT)

APPROVED: DIRECTOR, OF FACILITIES MANAGEMENT, DEPARTMENT OF PUBLIC WELFARE

APPROVED:

CHECKED BY DEPARTMENT OF GENERAL SERVICES

ARCH.	STRUCT.	M.E.C.	PLBG.	ELECT.	MISC.

COMMONWEALTH OF PENNSYLVANIA
DEPARTMENT OF GENERAL SERVICES
HARRISBURG, PENNSYLVANIA

PROJECT NO. D.G.S. A510-29

RENOVATION FOR EXPANSION OF FORENSIC UNIT BLDG. NO. 8

PHILADELPHIA STATE HOSPITAL
PHILADELPHIA, PENNSYLVANIA

DAVID S. TRUMS ASSOCIATES
ARCHITECTS & PLANNERS
1704 WALNUT STREET
PHILA. PA 19103

ADCOCKS MATZ ASSOCS. INC.
CONSULTING MECH. ENGINEERS
132 S. 15TH STREET
PHILA. PA 19103

SECOND FLOOR PLAN & DETAILS

DRAWN BY	DATE	DRAWING NO.
JMS	9/28/05	A2
CHECKED BY DSP	SCALE AS NOTED	

PLAN OF TOILET ROOM

(1/A3) RM. 228 SHOWN; 228 OPP. HAND.

1/4" = 1'-0"

PATCH EXIST. G.S.T. WALL AFTER REMOVAL OF PARTITION WITH NEW 2' G.S.T. TILE TO MATCH SURROUNDING. MATCH IN NEW TILE WITH EXIST. AS NEEDED.

PATCH DAMAGED CER. TILE AS REQUIRED @ FLOOR

REMOVE EXIST. 4 FOOT HIGH G.S.T. PARTITION

REPAIR

TOILET 228/234

NOTE: FOR REMOVAL OF EXISTING MECH. AND INSTALLATION OF SLOAN'S SEE MECHANICAL SPECS. AND DRAWINGS

NEW HOOKER BY MECH. CONT.

PLAN OF CORRIDOR

(2/A3) CONDITION AT 229/230 SHOWN; 229/227 OPP. HAND.

1/4" = 1'-0"

FLOOR TO RECEIVE CERD GST TILE.

NEW G.S.T. PARTITION DOOR & FRAME

CORRIDOR 229 230

CORRIDOR 229 227

NEW PARTITION TO MATCH SURROUNDING HIGH-LIGHT - EFFECT CORRIDOR ABOVE CEILING.

NOTE: CEILING, BOTH SIDES TO BE RE-CEILED WITH NEW G.S.T. EXISTING TILE TO MATCH PRE-EXISTING CONDITIONS.

PLAN OF STORAGE & LINEN RMS

(3/A3) RMS 222 & 222A SHOWN; RMS 221, 221A OPP. HAND.

1/4" = 1'-0"

NOTE:

- SECTIONS 22 WALLS EXTENDED TO UNDERSIDE OF OVERHEAD STRUCTURES. TYPICALLY SHALL BE UNCLADED STRUCTURAL TILE ABOVE EXISTING ACOUSTIC CEILING.

STORAGE 222/222A

SOILED LINEN 221/221A

SEE NOTE BELOW TITLE

NEW: EXISTING EXIST. WALL TO UNDERSIDE OF STRUCTURE. PATCH CEILING AS REQ.

NEW DOOR & CASING RM 222A ONLY

NEW PARTITION AT RMS 222/222A ONLY EXTEND TO UNDERSIDE OF STRUCTURE.

EXIST. PIPE CHASE

NOTE: FOR STORAGE & SOILED LINEN & ADJOINING ROOMS - PATCH EXISTING ACOUSTIC CEILINGS TO CONFORM TO PRE-EXISTING CONDITIONS AFTER INSTALLATION OF NEW WALL AND AREA EXTENSION OF EXISTING WALLS.

NOTE: EXISTING WALLS REDUCED 1'-0" TO UNDERSIDE OF STRUCTURE

NEW DOOR.

SET ANCHORS & PATCH DAMAGED TILE "EARTH" G.S.T.

CORRIDOR 235 236

DETAIL

(6/A3) 1/4" = 1'-0"

DETAIL IS TYPICAL AT ALL INSTANCES WHERE G.S.T PARTITIONS ARE TO BE REMOVED.

EXTENDED G.S.T.

EXISTING CEILING

RESTORE G.S.T. TILE WHERE PART IS REMOVED AT PILASTER.

EXIST. G.S.T.

EXISTING FLOOR LINE

ELEVATION

PLAN OF DINING ROOM

(4/A3) 1/4" = 1'-0"

(EXISTING, ... EASTER, CEILINGS) (OVER).

NOTE: EXISTING DOORS & FRAMES TO BE PAINTED.

EXISTING MULLION

REMOVE EXISTING PARTITION: PATCH FLOOR, BASE, WALLS & CEILINGS TO MATCH EXISTING

EXIST. C.T. FLOOR

EXISTING G.S.T. WALLS

FILL EXISTING OPENING TO MATCH EXIST. G.S.T. (BOTH SIDES)

SEE DET. 6/A3.

REMOVE EXISTING PARTITION: PATCH FLOOR, BASE, WALLS & CEILINGS TO MATCH EXISTING

DINING ROOM 109

FILL DEPRESSION WITH G.S.T. TO MATCH EXIST.

REMOVE EXIST. C.T. WAINSCOT TO EXPOSE EXISTING G.S.T. PUFF. WALL WITH 2' G.S.T. (SCAPE).

EXIST. CABINETS TO REMAIN. SEE MECH. DWGS.