GENERAL NOTES

Provide 2500# Concrete.
Between separate pourings of concrete, provide dowels equal in size and number to bars in the doweled member.
In continuous slabs or beams bend up bent bars and extend to quarter point of adjacent span. Lap all straight bars 12" bent bars in end spans to be hooked.
All spilled bars to be lapped 40 Diameters.
Top of slab generally 3" below finished floor line.
For hose lintels, interior & exterior, see Arch. Details.
For location of construction, pipe sleeves, ducts, etc., see Arch. & Mech. Details.
Provide 3-3/4" diagonal bars around openings not otherwise framed.
Day rooms and stair Parts to be 8"x8" 4-3/4" and 3/4" horizontal ties 12".
Fireproofing - Thickness:
Slab bars - 1"
Beam bars - 2"
Column bars - 2"
Foundation bars - 4"
Depress all slabs around urinals 2".

ALL DIMENSIONS AND MEASUREMENTS SHALL BE CHECKED AND VERIFIED BY THE CONTRACTOR AT THE SITE.

BUREAU OF ENGINEERING & CONSTRUCTION CHECKED BY			
ARCH.	STRUCT.	MECH.	ELEC.

GRAVELL & DUNCAN, R.E.s.

APPROVED
Commonwealth of Pennsylvania
DEPARTMENT OF WELFARE
Archi. [illegible] Date 10-11-49
Secretary _____ Date _____
Eugene R. Shelly M.D.
PROJECT-232

REVISED

APPROVED [illegible] 9/1/49
DEPUTY SECRETARY OF PROPERTY & SUPPLIES
APPROVAL RECOMMENDED [illegible] 9/1/49
SUPERVISING ARCHITECT BUREAU OF CONSTRUCTION
APPROVED [illegible] Secretary of Welfare
SUBMITTED Howell Lewis Shay
ARCHITECT
ACCEPTED
CONTRACTOR

SECOND FLOOR PLAN BLOCK "A"

BUILDING N-9
MAXIMUM SECURITY BUILDING
for MALE PATIENTS
PHILADELPHIA STATE HOSPITAL
PHILADELPHIA, PENNSYLVANIA
HOWELL LEWIS SHAY, A.I.A. REGISTERED ARCHITECT
1801 - PACKARD BUILDING, PHILADELPHIA, PENNSYLVANIA

DATE Sept. 16-48	COMMONWEALTH OF PENNA.	COMM. No.
SCALE 1/8"=1'-0"	JAMES H. DUFF, GOVERNOR	1369
DRAWN R.M.F.	DEPT. PROPERTY & SUPPLIES	SHEET No.
CHECKED	C. M. WOOLWORTH, SECRETARY	S-3
	HARRISBURG, PENNSYLVANIA	

3-6-14